

5. Ēkas norobežojošo konstrukciju laukumu aprēķins

Debesspuse	Norobežojošā konstrukcija	Tips	Garums, Platums	Augstums	Laukums	Perimētrs	Skaitis	Kopējais segmentu laukums	Kopā laukums	Kopā perimētrs	
			m	m	m ²	m	gab.	m ²	m ²	m	
Ziemeļi	Siena	ķieģelis 51	10,20	7,00	71,40		1	71,40	259,37		
			31,20	3,20	99,84		1	99,84			
			10,30	2,80	28,84		1	28,84			
			9,80	6,05	59,29		1	59,29			
	Logi	pvc	0,65	1,75	1,14	4,80	4	4,55	36,57		19,20
			1,65	1,82	3,00	6,94	9	27,03			
			0,50	0,50	0,25	2,00	1	0,25			
			0,90	1,82	1,64	5,44	1	1,64			
			1,15	2,70	3,11	7,70	1	3,11			
	Durvis	PVC	1,00	2,00	2,00	6,00	3	6	6	18,00	
Kopā siena (aprēķina laukums):								ķieģelis 51	216,80		
Dienvidi	Siena	ķieģelis 51	10,20	7,00	71,40		1	71,40	259,37		
			31,20	3,20	99,84		1	99,84			
			10,30	2,80	28,84		1	28,84			
			9,80	6,05	59,29		1	59,29			
	Logi	PVC	1,65	1,82	3,00	6,94	11	33,03	51,35		76,34
			1,30	1,30	1,69	5,20	9	15,21			
Kopā siena (aprēķina laukums):								ķieģelis 51	208,02		
Rietumi	Siena	ķieģelis 51	18,65	5,85	109,10		1	109,10	500,95		
			51,90	7,55	391,85		1	391,85			
	Logi	PVC	2,50	2,30	5,75	9,60	1	5,75	107,13		9,60
			1,65	1,85	3,05	7,00	32	97,68			
			1,00	1,85	1,85	5,70	2	3,7			
Kopā siena (aprēķina laukums):								ķieģelis 51	393,82		
Austrumi	Siena	ķieģelis 51	6,70	51,90	347,73		1	347,73	456,83		
			18,65	5,85	109,10		1	109,10			
	Logi	PVC	1,30	1,30	1,69	5,20	24	40,56	72,45		124,80
			0,65	1,75	1,14	4,80	1	1,14			
			1,25	4,10	5,13	10,70	6	30,75			
			1,45	2,65	3,84	8,20	2	7,69			
	Durvis	koks	1,00	2,00	2	6	3	6	6,00	18	
			Kopā siena (aprēķina laukums):								ķieģelis 51
Kopā (pvc logi):									267,50		
Kopā (koka durvis):									19,69	718,84	
ķieģelis 51									1189,34		

